

# PNNL Lab Home Results for CO2 Combi System Stress Tests

Cheryn Metzger, Joe Petersen, Josh McIntosh  
Pacific Northwest National Laboratory

Ken Eklund  
Washington State University

February 27, 2017  
Portland, OR  
PNNL-SA-124240




**Pacific Northwest**  
NATIONAL LABORATORY

*Proudly Operated by **Battelle** Since 1965*

# BACKGROUND

# Benefits: CO<sub>2</sub> as a Refrigerant (R744)

- ▶ Thermal lift at cold temperatures exceeds standard refrigerant capacity
- ▶ Flexible in different climate zones
- ▶ Non-flammable
- ▶ Global Warming Potential of 1 (vs 2,088)



# Past Lab Home Demand Response Experiments with Sanden CO<sub>2</sub> HPWHs


Experiment Metric	Unitary System	Split-System
Dispatchable Power (kW)	1.3	1.2
Recovery Energy Shift (kWh)*	2.65	2.95
Oversupply duration (hours)	6	6
Maximum off period while delivered temperature is met (hours)	6	12

\*Energy required to recover tank to set point after DR event

Opportunity!

GP Sullivan and JP Petersen. July 2015. [Demand-Response Performance of Sanden Unitary and Split-System Heat Pump Water Heaters](#) . PNNL - 24224, Pacific Northwest National Laboratory, Richland, WA.

# Project Participants





**Pacific Northwest**  
NATIONAL LABORATORY

*Proudly Operated by **Battelle** Since 1965*

# EXPERIMENTAL PLAN

# Lab Homes Characteristics

- ▶ Represent existing homes
  - 3 BR/2BA 1493-ft<sup>2</sup> double-wide, factory-built to HUD code
  - All-electric with 13 SEER/7.7 HSPF heat pump central HVAC + alternate Cadet fan wall heaters throughout
  - R-22 floors, R-11 walls & R-22 ceiling with composition roof
  - Incandescent lighting
  - Bath, kitchen, whole-house exhaust fans
  - Carpet + vinyl flooring
  - All electric
- ▶ Modifications include end-use metering, sensors, weather station, and three electric vehicle charging stations



During the heating season:


1. Does the system meet common space and water heating loads in these homes?
2. What is the impact on the system's ability to meet space and water heating needs when occupant-controlled variables such as thermostat settings, hot water draws, and hot water temperature settings are moved beyond average?
3. What is the DR oversupply mitigation capability and its ability to meet space and water heating loads?
  - a. When occupant-controlled variables are moved beyond average?



- ▶ Thermostat settings
  - Low: 65°F
  - Medium: 71°F
  - High: 80°F
  
- ▶ Water Temperature settings:
  - Low: 125°F
  - High: 135°F
  
- ▶ Water Load settings:
  - Low: 24 gpd
  - Medium: 46 gpd
  - High: 85 gpd


# Low Use – Daily Draw Profile

Typical Daily Draw Profile  
1 Occupant, 24 Daily Gallons



# Average Use – Daily Draw Profile


Typical Daily Draw Profile  
3 Occupants, 46 Daily Gallons



Window 1: 11 Gallons   Window 2: 9 Gallons   Window 3: 7 Gallons   Window 4: 13 Gallons   Window 5: 6 Gallons

# High Use – Daily Draw Profile

**Typical Daily Draw Profile**  
5 or More Occupants, 85 Daily Gallons



# Test Conditions


Test Name	Lab Home A (Control)				Lab Home B (Experiment)				
	Heating System	Heat Load	Water System	Water Load	Heating System	Heat Load	Water System	Water Load	DR Schedule
Stress High Flow	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	High	None
Stress Low Flow	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Low	None
Stress High Heat	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	High	Sanden HP	High	None
Stress Low Heat	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Low	Sanden HP	Low	None
Stress High Water T	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	None but water T= 140°F
DR 46 GPD	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	5 hrs off
DR 85 GPD	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	Medium	Sanden HP	High	5 hrs off

# EXPERIMENTAL SETUP




# Experimental Setup

## PNNL Lab Homes Combination System Component Layout




System design credit to Mark Jerome, CLEAResult





# Interior Heat Exchange System with Electric Forced Air Furnace



- ▶ Equipment procurement
- ▶ Limited space of water heater closet and utility room
- ▶ Pump leakage on Taco unit due to excess pressure → added expansion tank
- ▶ After some initial commissioning, looked closer at control strategy of Taco unit – factory setting was outside air reset control, changed to indoor temperature at thermostat for initial call for heat and on/off state
- ▶ Added extra pressure gauges in both homes to help diagnose problems
- ▶ Missing a pressure relief valve for one system
- ▶ Broke parts upon installation, needed to order new ones
- ▶ One Taco system ran continuously, even when HPWH was off and no call for heat → Dipswitch reconfigured
- ▶ Faulty mixing valve




**Pacific Northwest**  
NATIONAL LABORATORY


*Proudly Operated by **Battelle** Since 1965*

# INITIAL RESULTS

## High Water Heater Load: 46 GPD vs. 85 GPD




## Thermostat Set Point Increase: 71°F vs. 80°F




- Outdoor Temp
- Baseline Hall Temp
- Exp Hall Temp
- Base DHW Delivery Temp
- Exp DHW Delivery Temp

## DHW Set Point: 125°F vs. 135°F



- Outdoor Temp
- Baseline Hall Temp
- Exp Hall Temp
- Base DHW Delivery Temp
- Exp DHW Delivery Temp

## 46 GPD vs. 85 GPD with DR Event



- Outdoor Temp
- Baseline Hall Temp
- Exp Hall Temp
- Base DHW Delivery Temp
- Exp DHW Delivery Temp

- ▶ When outdoor temp is above 40°F, system can meet loads:
  - 85 GPD
  - 80°F thermostat set point
  - 135°F water heater set point
- ▶ System cannot meet loads consistently:
  - When outdoor temperature is below 40°F
- ▶ Inconclusive if system can meet loads consistently following a DR event if temperatures are above 40°F
- ▶ System favors space conditioning temperature over water heating temperature



# Future Work

- ▶ Technical report
- ▶ 1 page fact sheet
- ▶ Installation guidance
- ▶ Web content
- ▶ Power point presentation for funders to share with other utilities

# THANK YOU!

Contact Information:

Cheryn Metzger PE PMP LEED AP

[Cheryn.metzger@pnnl.gov](mailto:Cheryn.metzger@pnnl.gov)

707-623-7091

Let me know if you would like to be added to the new Lab Homes Newsletter!